

Item Number	Item Description	Item Quantity	Unit of Measure	Consignee ID	Delivery Period (In number of days)
1	Item Code : 1200005137 AIR CONDITIONER, HI-WALL SPLIT TYPE, INVERTER BASED, 2 TR CAPACITY, BEE 5 STAR RATING, WITH COPPER CONDENSER COIL AND REMOTE ALONG WITH STANDARD ACCESSORIES HAVING 3 MTRS OF COPEER PIPE. and Electrical cable OPERATING ON SINGLE PHASE 230 VOLTS, 50 HZ AC SUPPLY, ECO FREINDLY REFRIGERANT GAS including gas charging work, If additional Gas is required, at various locations under jurisdiction of EESD. works includes installation of indoor and outdoor units installation of drain pipe, copper pipes with insulation and cable all covered with white tape clamped for full length to the instructions. Standard installation (Scope of installation as per STC attached) with uninstillation of existing A C included in this item. The uninstalled ACs will be handed over to EESD.	29	each	mrarkhan	45 days
2	Item Code : 1200008520 Supply and delivery of additional copper pipes with nitrile insulation for installation of Split A.Cs	183	Meter	mrarkhan	45 days
3	Item Code : 1200008501 Supply and delivery of additional cable for installation of Split A.cs	282	Meter	mrarkhan	45 days
4	Item Code : 1200008530 Supply and delivery of hard PVC Drain pipe for installation of Split A.C.s	272	Meter	mrarkhan	45 days
5	Item Code : 1200008540 Supply, Delivery & Installation of L-Bracket / table top stands for outdoors units at required locations to the instructions	29	each	mrarkhan	45 days
6	Item Code : 1200008521 Provision of Necessary hole/core cutting at walls/Wooden frames/metal frames etc. at various locations for laying of copper pipe, cable & drain pipe from indoor unit to outdoor unit along with cementing work for closing hole Internally & externally to the Instructions.	29	each	mrarkhan	45 days
7	Item Code : 1200008665 Supply, Delivery, Laying, Saddling of 4CX35 SQ.MM. XLPE-A-PVC armored Cable with copper conductors along with suitable size of earth GI wire & end to end terminations to the instructions. (from Mains or nearest supply source to MCBDB panels)	100	Meter	mrarkhan	45 days
8	Service Code : 8200012272 SUPPLY, DELIVERY,INSTALLATION, TESTING & COMMISSIONG OF 3 PHASE MCB-DB DOUBLE DOOR WITH MCB 4 POLE 100 AMPS - 1 NO, DOUBLE PLE MCB "C" SERIES 20 AMPS - 06 NOS, HOUSED IN SHEET ENCLOSURE (1.5MM THICK) WITH EARTH TERMINAL COMPLETE WITH ALL ACCESSORIES	2	Job	mrarkhan	45 days
9	Service Code : 8200012271 WIRING BY PVC CASING AND CAPPING WIRING SYSTEM USING RIGID PVC CASING AND CAPPING & FR PVC INSULATED SINGLE CORE COPPER CONDUCTOR WIRES OF SIZE 3C X 4 SQ MM (PHASE, NEUTRAL, AND EARTH), 660/1100 VOLTS GRADE FOR POWER SOCKET POINT AS PER INSTRUCTIONS. FR-PVC INSULATED COPPER CONDUCTOR SINGLE CORE WIRES TO BE TERMINATED IN INDUSTRIAL METAL CLAD PORCELAIN SOCKET, 20A, 230V and 1 no. 20A, 230V, SPMCB UNIT C-SERIES HOUSED IN SEPARATE SHEET STEEL ENCLOSURES INCLUDING 3 PINS METAL CLAD PLUG TOP AS REQUIRED FOR NEW AIR CONDITIONER UNITS. (Independent circuit to be tapped from the MCBDB panel at sr.no.8 to the instructions)	8	Job	mrarkhan	45 days